

An example of a Design of small Gravity Dams

by Hailu Yemanu, Chief Engineer of the Awash Valley Authority and Lecturer of Fluid Mechanics and Hydraulics at the Engineering College, Haile Selassie I University

1. Introduction

The purpose of this paper is to consider and discuss the merits of the methods employed in the consideration and design of a concrete diversion dam designed by the writer with the purpose of diverting a maximum flow of 1.5 m³/sec from the Culfo River for the agricultural irrigation of approximately 1250 hectares at the Arba Minch Farm in Gemu Gofa Province.

It is of course fully appreciated that there are numerous and wide variations in the criteria which can be employed to design such type of gravity dams as carried out in various parts of the world and by numerous engineers.

However, it is suggested that the criteria borne in mind in the design of the small dam which is the subject of the following notes may be of value in considering the design of similar diversion or gravity dams of varying sizes.

2. Hydrogeological data

Five investigation boreholes have been drilled along the proposed axis of the dam to a depth ranging between 15 and 31.5m.

On the left side of the Valley the soil consists of basalt boulders with gravel sand and silt forming a sort of soft conglomerate.

On the right side sandy silty formations prevail, occasionally including some gravel.

The frequent alternation of thin layers (sandy — silts and silty — sands in general) did not suggest the opportunity of laboratory tests of undisturbed samples, but the visual inspection of the latter show fairly good degree of relative density or consistency.

The intermediate borehole at the centre of the axis of the dam has the same features as the boreholes on the left side of the valley down to 5m. depth, while the underlying formations are similar to those found on the right side.

According to the water tests carried out in the abovementioned boreholes the permeability coefficient K is generally low from the seepage point of view (order of 10^{-4} to 10^{-5} cm/sec). Values of K in the order of 10^{-6} cm/sec often indicate that the strata is practically impervious.

On the other hand the dissipation of excess pore pressures produced by loading will be a short term phenomenon, and therefore the stability analysis against shear failure may be performed in terms of effective stresses, assuming an average value for the internal angle of friction:

$$\phi = 30^\circ$$

with no cohesion assumed.

3. Design data

On the basis of the limited hydrological observations of the river and the irrigation water requirement ($Q_{\max} = 1.5 \text{ m}^3/\text{sec}$) for the above mentioned area of 1250 ha to be commanded the following design data have been established:

dam crest elevation	108.70 m
length of spillway	33 m
maximum head of spillway	1 m
	(Elev. 109.70)
maximum estimated flood	66 m ³ /sec

With the foregoing data the following was proposed for the preliminary design of the dam:

foundation width of the dam	4.40 m
foundation depth	105.50 m elev.
upstream ground elevation	107.00 m
downstream ground elevation	106.65
	(rock rip rap)
system of piles	5 ranges

After obtaining the results of the geohydrological investigation of the dam site the preliminary design of the diversion dam shown in Fig. 1 was revised for safety against piping, shear failure, excessive seepage and up lift under the dam and also checked against over turning and sliding effects.




Fig. 1 — Preliminary Design of the Diversion Dam

4. Safety against Piping




The exit gradient generally provides the most significant criterion design for the factor of safety with respect to piping.

For a depressed structure on a permeable base of infinite extent the exit gradient may be analytically calculated by Harr's expression:

$$i_e = \frac{\alpha H}{\pi D_f} \quad (1)$$

where:

- H = hydraulic head loss
- D_f = Embedment depth of structure
- α = coefficient to be determined according to Harr as a function of the ratio D_f/B where B is the width of structure (Fig. 2).



M IS A CONSTANT FUNCTION OF $\frac{D_f}{B}$ OR $\frac{B}{D_f}$
(AFTER PAVLOVSKY)

Fig. 2 — Determination of the Coefficient

The weighted-creep theory as developed by Lane could also be employed as criteria for the design of low concrete dams on pervious foundations to be safe against piping and uplift pressures. Although this is an empirical method, considerable confidence has been placed in it by many engineers and it has been successfully used for the design of many structures.

We consider the following expressions for the calculation of hydraulic gradient:

$$I_e = \frac{H}{\sum B} \quad \text{Bligh's equation}$$

$$C = F_s = \frac{I_{cr}}{I_e} \quad (2)$$

$$I_e = \frac{H}{\frac{1}{3}B + \sum t} \quad \text{Lane's equation}$$

where:

- H = hydraulic head loss
- B = Horizontal section of the line of creep
- t = Vertical section of the line of creep
- C = safe weighted creep ratio or expressed as coefficient of safety factor F_s
- I_{cr} = critical gradient, as per Terzaghi = 1.

TABLE 1 — Weighted-Creep Ratio

Type of Material	Safe Weighted Creep Ratio	
	Lane's Value of $C = F_s$	Bligh's Value of $C = F_s$
Very fine sand or silt	8.5	18
Fine sand	7.0	15
Medium sand	6.0	—
Coarse sand	5.0	12
Fine gravel	4.0	—
Medium gravel	3.5	—
Gravel and sand	—	9
Coarse gravel including cobbles	3	—
Boulders with some cobbles & gravel	2.5	—
Boulders, gravel & sand	—	4-6
Soft clay	3	—
Medium clay	2	—
Hard clay	1.8	—
Very hard clay or hard pan	1.6	—

From the preliminary design data (Fig. 1) we have:

- $D_f = 1.15$ m downstream side
- $B = 4.40$ m
- $H = 2.70$ m (max. upstream water elevation 109.70 m minus downstream water level supposed at elevation 107.00 m).

Employing Harr's criteria from (1) and from (Fig. 2) $\alpha = 0.5$ and therefore:

$$I_e = \frac{\alpha H}{\pi D_f} = \frac{0.5 \times 2.70}{3.14 \times 1.15} = 0.374$$

The factor of safety in our case is:

$$F_s = \frac{I_{cr}}{I_e} = \frac{1}{0.374} = 2.67$$

This is too low for any type of pervious soil, compared with the minimum allowable value of 4 according to the criteria of Lane (Table 1.) When fine sand is present, as in our case, Khosla, Bose and Taylor recommend a safety factor of at least 6 and it may be even raised to 10.

From our preliminary design F_s is very low and it was required to increase the safety factor. An increase of F_s can be obtained by enlarging and deepening the structure. The enlargement alone does not bring about convenient solution as shown in Table 2.

Maintaining D_f constant and varying B we calculate F_s :

TABLE 2

B (m)	F_s
4.40	2.67
6.00	3.04
8.00	3.45
10.00	3.72
12.80	4.00
23.00	6.00

More advantage can be obtained by increasing the depth D_f as shown by Table 3. In this case two alternatives were considered:



$$B = 4.40 \text{ m} \quad \text{and} \quad B = 6.00 \text{ m}$$

TABLE 3

$B = 4.40$ m		$B = 6.00$ m	
D_f (m)	F_s	D_f (m)	F_s
1.15	2.67	1.15	3.04
1.65	3.56	1.65	3.84
2.15	4.24	2.15	4.72
2.65	4.95	2.65	5.32
3.15	5.82	3.15	6.20

The above calculations refer to structures without cut-offs or sheet pilings but the result is not likely to be much different when the width of the structure and the depth of vertical elements are not very important; anyway the safety factor would be underestimated, if D_f represents the depth of vertical elements.

In our case a sheet piling may meet with some difficulty due to the presence of boulders, and the execution of two cutoff walls (one upstream and one downstream) will be more suitable.



On the basis of the results of the foregoing analysis the following elements have been fixed for the final design of the diversion dam (Figs. 3 & 4)

$$\begin{aligned} \text{base width } (b) &= 6.00 \text{ m} \\ \text{base elevation} &= 105.00 \text{ m} \end{aligned}$$

$$\begin{aligned} \text{Cutoff depth below downstream ground} \\ \text{level } (D_f) &= 3.15 \text{ m}. \end{aligned}$$

According to figures in Table 3, calculated following Harr's criteria, the factor of safety is 6.2 for the most unfavourable case of maximum spillway head. This can be considered satisfactory. Following Eligh's criteria the safety factor,

$$F_s = \frac{15.05}{2.70} = 5.57$$

And according to Lane,

$$F_s = \frac{11.65}{2.70} = 4.3,$$

Both of these values are greater than four. Considering $\alpha = 0.51$ when the water is at dam crest level:

$$I_e = \frac{\alpha H}{\pi D_f} = \frac{0.510 \times 2.05}{3.14 \times 3.15} = 0.106$$

$$F_s = \frac{I_{cr}}{I_e} = \frac{1}{0.106} = 9.5$$

F_s rises to about 10.

5. Stability against Shear Failure

The ultimate bearing capacity of a foundation with inclined resultant load applied to a granular subsoil, is given by the Erinch Hansen equation:*

$$\begin{aligned} q_u = 0.5 \gamma N_r B \left[1 - 0.3 \frac{B}{L} \right] \left[1 - 1.5 \frac{H}{N} \right]^2 + \\ \gamma D_f N_q \left[1 + 0.2 \frac{B}{L} \right] \left[1 + 0.1 \frac{D_f}{B} \right] \\ \left[1 - 1.5 \frac{H}{N} \right] \end{aligned} \quad (3)$$

where:

- B = width of foundation
- L = length of foundation
- H = horizontal forces acting on the soil
- N = vertical forces acting on the soil
- D_f = depth of foundation
- γ = submerged density of soil
- N_r, N_q = bearing capacity factors, functions of the internal angles of friction of the soil (ϕ), according to Terzaghi.

When the resultant, inclined force $R = f(H, N)$ is eccentric, B must be substituted with the reduced effective width:

* This is an extension of Terzaghi formula:
 $q_u = 0.5 \gamma N_r B + CN_c + \gamma D_f N_q$,
 where for cohesionless soil $CN_c = 0$,
 N_c being bearing capacity factor.

$$B' = B - 2.e \quad (4)$$

where e represents the eccentricity.

Considering the final adopted design of the dam (Section 4) and the nature of the soil (Section 2) we arrive at:

$$\begin{aligned} B' &= 6.00 - 2e & L &= 33 \text{ m} \\ D_f &= 3.15 \text{ m} & N_r &= 20 \\ \phi &= 30^\circ \text{ (determined in} & N_q &= 22 \\ &\text{Section 2)} & \gamma &= 1 \text{ ton/m}^3 \end{aligned}$$

The bearing capacity factors N_r, N_q are determined from Fig. 5.

As concerns the stress conditions, two cases have been considered:

CASE "A" (Fig. 3)

Upstream water elevation = 108.70 m (dam crest),

Downstream water elevation = 106.65 m (rock riprap top level).

Full water thrust is considered on both upstream and downstream sides (S_w and S'_w); earth pressures compensating mutually.

Vertical resultant N including saturated weight of soil between cutoff walls and full uplift force " U " at cutoff base level (trapezoidal diagram with upstream pressure of 5.20 ton/m² and downstream value of 3.15 ton/m²):

Total load (structure + soil between cutoffs)	$P = 51.2$ ton
Uplift force at cutoffs base level	$U = 25.1$ ton
Resultant vertical force	$N = 26.1$ ton
Water thrust on upstream side	$S_w = 13.5$ ton
Water thrust on downstream side	$S'_w = 5.0$ ton
Resultant horizontal force	$H = 8.5$ ton

Taking moment of forces about the upstream cutoff wall toe, moment arm of the resultant inclined force R :

$$a = \frac{M_1 N + M_2 H}{N} = 3.20 \text{ m.}$$

Eccentricity of the resultant inclined force R :

$$e = a - \frac{B}{2} = 3.20 - 3.00 = 0.20 \text{ m.}$$

According to equations, (3) and (4) and to the magnitude and position of forces shown in (Fig. 3) the following values of ultimate bearing capacity have been obtained:

$$q_u = 52.8 \text{ ton/m}^2/\text{m.} \quad \text{from (3)}$$

The applied average pressure to be compared with q_u is given by the expression:

$$P_o = \frac{N}{B'} = \frac{N}{B - 2e} \quad (5)$$

According to Equations (4) and (5), we have

$$P_o = 4.65 \text{ ton/m}^2/\text{m.}$$

MOENCO

The Motor and Engineering Company of Ethiopia Ltd.
(Member of INCHCAPE Group)

Authorized dealers
for the Ethiopian Empire:

OPEL Cars & Trucks.

OLDSMOBILE

BEDFORD Trucks

FRIGIDAIRE

PONTIAC

VAUXHALL Cars

G. M. C. Trucks

G. M. Diesel

CADILLAC

DELCO-REMY - A.C.

DUPONT - FREON GAS

VREDESTEIN TIRES

I. T. T. Corporation

ZANUSSI Products.

THOMAS DE LA RUE & Co.

INGERSOLL - RAND

HOBART - WELDERS.

ROGERS TRAILERS.

KOEHRING EXCAVATORS - CRANES - DRAGLINES

YALE FORK LIFTS & MACHINERY

POCLAIN EXCAVATORS.

BARBER - GREENE

CHEVRON ANGLE IRON

FORD TRACTORS & EQUIPMENT

TOYOTA VEHICLES & LAND CRUISERS.

WABACO - GRADERS - TOURNA TRACTORS
SCRAPERS ETC.

ALLIS-CHALMERS ENGINEERING PRODUCTS.

FAILING DRILLING RIGS (WABCO)

CONSTRUCTION EQUIPMENT, PUMPS, SILOS ETC.

STONE CRUSHERS, IRRIGATION, ETC.

WATER TREATMENT PLANTS

የኢትዮጵያ ፡ የሞተርና ፡ የመሳሪያዎች ፡
ማኅበር ፡ ሊ.ሚ.ት.ድ ፡

Automotive Dept.

Pharmaceutical Dept.

Engineering Dept.

P. O. Box 1767 — ADDIS ABABA

Cable 'MOENCO'

Telex: 1019

Telephones:

Management 45708

Automotive Dept. 46440

Accounts 45674

Pharmaceutical Department 45680

Engineering Department 47557

Garage and Spare Parts Dept. 46491

Custom Warehouse 46358

Branch: ASMARA

P. O. Box 842 — Tel. 10384

and the following safety factor is obtained:

$$F_s = \frac{q_u}{P_o} = 11.40$$

The stability against shear failure is then ample even in the most unfavourable conditions.

Safety factor:

$$F_s = \frac{q_u}{P_o} = 4.27$$

The stability against shear failure is also ample in the above indicated Case (B).




Fig. 5 — Chart showing relation between ϕ and bearing capacity factors

Loaded strip, width B

Total load per unit length of footing

$$\text{General shear failure: } Q_d = B \left(CN_c + \gamma D_f N_q + \frac{1}{2} \gamma B N_r \right)$$

Local shear failure:


$$Q'_d = B \left(\frac{2}{3} CN'_c + \gamma D_f N'_q + \frac{1}{2} \gamma B N'_r \right)$$

Square footing, width B

Total critical load:

$$Q_{ds} = B^2 (1.3 CN_c + \gamma D_f N_q + 0.4 \gamma B N_r)$$

$$\text{Unit shear resistance, } S = c + \sigma \tan \phi$$



CASE "B" (Fig. 4)

Upstream water elevation = 109.70 m
(maximum spillway head).

Downstream water elevation = 107.00 m
(0.35m above riprap top).

Horizontal water thrust is calculated according to the new conditions and Vertical resultant force N as in case (A).

It is very unlikely that the maximum head condition may last for such a long time to produce uplift pressure worse than that considered in case (A). Therefore U is taken as in case (A).

$$\text{Vertical forces } \begin{cases} P & = 51.2 \text{ ton} \\ U & = 25.1 \text{ ton} \\ N & = 26.1 \text{ ton} \end{cases}$$

$$\text{Horizontal forces } \begin{cases} S_w & = 18.8 \text{ ton} \\ S'_w & = 5.0 \text{ ton} \\ H & = 12.7 \text{ ton} \end{cases}$$

Proceeding as in the previous Case (A)

Eccentricity of resultant force R :

$$e = 0.68 \text{ m}$$

Applied pressure at cutoffs base level:

$$P_o = \frac{N}{B - 2e} = 5.63 \text{ ton/m}^2.$$

6. Seepage

According to the results of permeability tests the quantity of seepage under the dam is likely to be low, on condition that the passage of water along or near the soil structure contacts is prevented.

The contacts between soil and structure which may have been disturbed or loosened by excavations would require treatment up to certain depth.

Grouting might solve the problem but for such a small dam this solution was considered to be expensive.

Since the permeability tests indicate low seepage loss and the cutoff walls also reduce this loss, it was considered that the seepage would not be a serious problem. However, in order to seal the contacts between soil and structure, it was proposed to substitute the disturbed natural soil at the upstream cutoff wall by compacted mixture of clay, sand and gravel. The downstream cutoff wall side was provided with inverted filter as shown in Fig. 6.

Measures taken to minimize seepage losses also reduce considerably the uplift effect. The cutoff walls, the compacted mixture of clay, sand and gravel at the upstream face of the structure would increase greatly the "creep length". This together with the inverted filters at the downstream face of the cutoff wall reduces considerably the uplift effect under the dam.

7. Overturning

Since the resultant of vertical forces is much higher than the resultant of horizontal forces in both cases A & B (Section 5) the structure is safe against overturning.

Taking moment about of the downstream cut-off wall toe:

$\frac{H}{N}$ is equal to or less than "f"

$$\text{Case A: "f"} = \frac{8.5}{26.1} = 0.325$$

$$\text{Case B: "f"} = \frac{12.7}{26.1} = 0.485$$




Fig. 6 — Final design of the Diversion Dam

Case A

$$F_s = \frac{MH}{MN} = \frac{2.15 \times 8.5}{3.50 \times 26.1} = 0.2, \text{ less than } 1$$

Case B

$$F_s = \frac{MN}{MH} = \frac{2.40 \times 12.7}{3.50 \times 26.1} = 0.33, \text{ less than } 1$$

The factor of safety against overturning is sometimes defined as the ratio of the tightening moments to the overturning moments about the toe of the dam. When so defined all excepting the direct foundation reaction are deemed active. Ordinarily the factor of safety against over-turning is between 2 and 3.

$$\text{Case A: } F_s = \frac{MN}{MH} = 5, \text{ greater than } 3$$

$$\text{Case B: } F_s = \frac{MN}{MH} = 3.3, \text{ greater than } 3$$

8. Sliding

The allowable sliding factor is the coefficient of static friction between two sliding surfaces reduced by an appropriate factor of safety. If "f" represents the allowable sliding factor, a dam is considered safe against sliding when

Our case represents for permissible "f" — concrete against gravel, coarse sand and boulders.

Furthermore the cutoff walls prevent displacement as could be observed from Figs. 3, 4 and 6.

Exact values for coefficients of static friction cannot be determined without the benefit of laboratory tests, but the allowable sliding factors given below which include ample factors of safety for concrete against sliding on the various foundation materials may be used as a general guide:

Material	f
Sound rock, clean and irregular surface	0.8
Rock, some jointing and laminations	0.7
Gravel and coarse sand	0.4
Sand	0.3
Shale	0.3
Silt and clay	testing required

9. Conclusions

The final design of the diversion dam is safe against piping, shear failure, excessive seepage, uplift, overturning and sliding effects.

Piles are not necessary for stability against sliding or shear failure as discussed in section 5.

The presence of a double cutoff wall and an adequate compacted mixture of clay, sand and gravel at the upstream side of the cutoff wall and the graded inverted filter at the downstream side of the cutoff wall will prevent piping, excessive seepage and uplift effect under the dam.

The downstream rock riprap must be sufficiently thick and long in order to prevent erosion near the dam by the over flowing water and for the purpose gabions have been recommended. But erosion may still take place beyond the protected zone. In this case the toe of the valley slopes should also be protected by rockfills and periodically repaired as necessary.

REFERENCES:

- (1) Geotechnical Report L — 1748, Ing. Giovanni Rodio, Sp.A., Italy, 1966.
- (2) Design of Small Dams — Bureau of Reclamation, U.S.A., 1965.
- (3) Soil Mechanics in Engineering Practice — Terzaghi & Peck, U.S.A., 1962.
- (4) A General Formula for Bearing Capacity — J. Brinch Hansen, Technical University of Denmark, 1962.
- (5) Foundations of Structures — General Subjects and Foundations Other Than Piled Foundations — Proceedings of the Fourth International Conference on Soil Mechanics and Foundation Engineering, London, 1957.
- (6) Ground Water and Seepage — Harr, Milton E., U.S.A., 1962.

Allgemeine Elektricitäts Gesellschaft

A. E. G.

Berlin (West)
Frankfurt (Main)
West Germany

Agents for the Ethiopian Empire

SEFERIAN & Co. (Ethiopia) Ltd., S.C.

P. O. Box 64 - Tel. Nos. 48100-1-2, 44719 - ADDIS ABABA